

**BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE**

Office of the Executive Engineer Dasarahalli Division

Schedule - B

BBMP/2021-22/RD/WORK_INDENT48422

ME OF WORK: Filling of pot holes in main roads and cross roads in Dasarahalli ward no

15

	Description of work	Unit	Qty	Rates Quoted by Contractor Sri HOLENARASIPUR SRINIVAS GIRISH (HVK ENTERPRISES)	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Providing, laying, spreading and compacting cushed Cum stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub- base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. With all lead & lift charges & as per direction of Engineer-In-Charge of Work	Cum	364.39	1500.0	Rupees One Thousand Five Hundred Only
2	Filling Pot-holes and Patch Repairs with Bituminous. Concrete, 40 mm Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, applying tack coat on the sides and base of excavation at 2.5kg/10sqm as per clause 500.3, filling back the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 including cost of materials, labour, HOM complete as per specifications. With all lead & lift charges & as per direction of Engineer-In-Charge of Work	Sqm	382.39	250.0	Rupees Two Hundred Fifty Only

HSASPS

Executive Engineer.